



KALYANI HEAVY FORGINGS PVT. LTD.

Plot No. C-12, MIDC Bhosari Industrial Area, Pune - 411 026, Maharashtra, INDIA
Tel: +91-20-XXXX-XXXX | Email: projects@khforgings.com | GST: 27AABCK1234X1ZY

TECHNICAL INQUIRY — ELECTRIC OVERHEAD TRAVELLING CRANE

Document Ref. No. :	KHF/PROJ/26-27/042	Date :	14-Aug-2026	Rev. :	00
Project :	New Heavy Machining Bay — Unit III	Classification :	CONFIDENTIAL	Pages :	01 of 01

1. SCOPE OF WORK

Kalyani Heavy Forgings Pvt. Ltd. invites sealed technical and commercial offers from reputed crane manufacturers for the **Design, Manufacture, Factory Testing, Supply, Erection, and Commissioning** of one (1) No. Double Girder Electric Overhead Travelling (EOT) Crane for our new **Heavy Machining Bay — Unit III** at our Bhosari manufacturing facility, Pune. The crane shall be designed and manufactured strictly in accordance with **IS:3177 (Latest Edition)** for EOT Cranes and **IS:4137** for Hook Suspension, and shall comply with all applicable Indian Standards. The vendor shall be responsible for the complete turnkey supply including civil interface details, gantry rail, conductor rail (DSL) system, and a mandatory 12-month on-site performance warranty from the date of commissioning.

2. TECHNICAL PARTICULARS

PARAMETER	SPECIFIED VALUE / REQUIREMENT
A. GENERAL CONFIGURATION	
Crane Type	Double Girder Electric Overhead Travelling (EOT) Crane
Quantity	1 No. (One Number)
Installation	Indoor New Heavy Machining Bay — Unit III, Bhosari Plant
Applicable Standard	IS:3177 (Latest Ed.) / IS:4137 / IS:3443
B. LIFTING CAPACITY	
Main Hoist (MH) Capacity	35 Tonnes (Safe Working Load)
Auxiliary Hoist (AH) Capacity	10 Tonnes (Safe Working Load)
C. CRANE DIMENSIONS	
Span (Rail CRS to Rail CRS)	18.5 Metres
Lift Height — Main Hoist (MH)	9.0 Metres (from floor level to top of hook)
Lift Height — Aux. Hoist (AH)	9.5 Metres (from floor level to top of hook)
Bay Length (LT Travel)	60.0 Metres
D. OPERATING SPEEDS	
Main Hoist (MH) Speed	3.0 m/min (Full Speed)
Auxiliary Hoist (AH) Speed	5.0 m/min (Full Speed)
Cross Travel (CT) Speed	15.0 m/min
Long Travel (LT) Speed	25.0 m/min

Micro / Creep Speed	Required on Hoists Only — 10% of rated hoist speed <i>i.e. MH: 0.3 m/min, AH: 0.5 m/min</i>
E. DUTY CLASS & ENVIRONMENT	
Duty Class	Class IV (M8) as per IS:3177-1999 / FEM 1.001
Ambient Temperature	50 deg C Maximum
Motor Insulation	Class F Insulation, Temperature Rise limited to Class B
Motor CDF / Starts	40% CDF, 150 Starts per Hour, 6-Pole
F. ELECTRICAL & CONTROL	
Power Supply	415V +/-10%, 3 Phase, 50 Hz +/-3%, AC
Control Voltage	110V AC (preferred) or 24V DC
Operation / Control	Radio Remote Control (Primary) with Pendant Push Button Station (Backup) <i>Both to be supplied. Pendant to have emergency stop and all motion controls.</i>
VVVF Drives	Required on ALL Motions (MH, AH, CT, LT) <i>Variable Voltage Variable Frequency drives for smooth acceleration / deceleration</i>
DSL Conductor System	Shrouded Bus Bar — Copper Conductor (Full Bay Length) <i>Supplier to supply and erect for full 60M bay length</i>
Motor Make (Preferred)	BHEL / CGL / KEC / Alstom (any approved make)

3. SPECIAL REQUIREMENTS & MANDATORY FEATURES

- **Anti-Collision System** — Mandatory. Automatic slow-down and stop when two cranes approach within a safe distance. Vendor to propose suitable system with proximity sensors or laser-based detection.
- **Load Limiter on Both Hoists** — Electronic / mechanical overload protection device on MH and AH. Crane must trip and alarm if load exceeds 110% of SWL. Test certificates to be submitted.
- **Under-Bridge Flood Lights** — Minimum 4 Nos. × 250W LED flood lights mounted under bridge girder for illuminating the working area below the crane. IP65 rated.
- **Centralized Lubrication System** — For all accessible greasing points on the crane (wheels, bearings, rope drum shaft). Manual grease gun ports acceptable for rope drum grooves.
- **Anti-Sway / Anti-Swivel Hook Lock** — Safety latch on both MH and AH hooks. Hook block to have anti-swivel arrangement for controlled load handling.
- **Full-Span Maintenance Platform** — Walkway platform with handrails on both sides of bridge for maintenance access. Platform to conform to IS:1875.


4. MANDATORY SUBMISSION WITH OFFER

1. General Arrangement (GA) Drawing indicating all major dimensions, lift heights, hook approaches, and wheel loads.
2. Technical data sheet for motors, gearboxes, brakes, and wire rope proposed.
3. List of mandatory spare parts with unit prices (valid for 2 years from commissioning date).
4. Quality Assurance Plan (QAP) and list of applicable inspection and test procedures.
5. Factory Acceptance Test (FAT) procedure and load test methodology.
6. Reference list of minimum 5 similar capacity cranes commissioned in last 5 years.
7. Deviation list (if any) against this specification — nil deviation preferred.

5. COMMERCIAL & DELIVERY TERMS


Offer Validity	90 Days from date of offer submission
Delivery Period	20 Weeks from date of Purchase Order (Ex-works)
Erection & Commissioning	4 Weeks from date of delivery at site
Warranty Period	24 Months from date of successful commissioning
Payment Terms	30% Advance with PO — 60% against Pro-forma Invoice before dispatch — 10% after commissioning
Price Basis	Firm & Fixed. No price escalation shall be entertained.
Offer Submission	Hard copy + Soft copy (PDF) to be submitted at our Pune office
Offer Due Date	05-September-2026 by 17:00 hrs IST

Prepared by




A. Kulkarni
Engg. Manager

Checked by




R. Deshmukh
Sr. Manager — Projects

Approved by



V. Marathe
VP — Manufacturing

Authorized Signatory



S. Kalyani
Director — Operations

This document is the property of Kalyani Heavy Forgings Pvt. Ltd. and is issued for tender purposes only. Recipients shall treat this as CONFIDENTIAL.
Reproduction or distribution without written consent is prohibited. Doc Ref: KHF/PROJ/26-27/042 | Rev: 00 | Date: 14-Aug-2026